

REQUEST FOR PROPOSAL (RFP) ADDENDUM

RFI Response: 3/30/26

Water Main Installation & Hydrant Improvements

Project: Mill Street Bridge Water Main Replacement

Owner: Town of Shandaken / Pine Hill Water District

Location: Pine Hill, Town of Shandaken, Ulster County

Send all site visit requests and enquiries by email to:

Kyle Steen, Pine Hill Water District Superintendent
Steen@shandaken.us

Send all bids by mail or in person by **3:00pm April 6, 2026**, to:

Joyce Grant, Shandaken Town Clerk
7209 NY-28, Shandaken, NY 12480
townclerk@shandaken.gov

Road Repair Spec:

All trench restoration shall conform to NYSDOT Section 404 (Hot Mix Asphalt)

Use:

8"-12" Compacted crushed stone (Type 2)

2.5"-4" binder course

2" top course

Install in lifts, properly compacted

Apply tack coat between lifts

Restore to existing pavement thickness or greater

Patch width: trench width + 2'

Road repair and infill are both still to be priced as options.

Carting of Excavated Materials:

For the purpose of pricing, assume that excavated materials which will not be reused will be carted to one of two Town of Shandaken Highway Yards located at or near 48 NY-42 Shandaken, NY. Alternatively, contractors may retain all or part of the excavated materials for their own use.

Bonding:

For the purpose of the bid, please use your quote to determine the size of the bond needed. There is no estimate from the Town for this purpose.